

PERFORMANCE RESULTS

Turley Bros
7 Corcreechy Road, Newry, Co. Down, Northern Ireland

EN 12566-1
Part 1: Prefabricated septic tanks
Results corresponding to EN 12566-1 and S.R. 66

PIA-SR66-1612-1131

Turley Bros Septic Tank

Material	Concrete
Structural behaviour (vertical load test)	Pass (for dry ground conditions only)
Watertightness	Pass
Nominal capacity	3 m ³ (3,314 l)
Hydraulic efficiency	99.98 % (without filter)
Durability	Pass

Performance tested by:

PIA – Prüfinstitut für Abwassertechnik GmbH
(PIA GmbH)
Hergenrather Weg 30
52074 Aachen, Germany

This document replaces neither the declaration
of performance nor the CE marking.



Notified Body
No.: 1739



Certified according to
ISO 9001:2008




Prüfinstitut für Abwassertechnik GmbH
Geprüft - tested - teste

Elmar Lancé

December 2016



Turley Bros Septic Tank range and its referring test reports:

Nominal capacity Usable Capacity Population equivalent (PE)	Drawing of model of the range	Watertightness and Nominal Capacity (EN 12566-1 Annex A)	Hydraulic Efficiency (EN 12566-1 Annex B)	Structural Behaviour (EN 12566-1 Annex D)	Durability
<p>3 3,314 l 8</p>		<p>Pass PIA2014-WD/NC-1403-1015</p>	<p>Pass PIA2014-HWG-1403-1015</p>	<p>Pass PIA2014-ST-BT-1403-1015 For dry ground conditions only, 0.70 m installation depth from inlet invert</p>	<p>Pass PIA2016-DH-1606-1069.01</p>

